

We Renew Energy

CONTENTS

A. SOLAR EXPLAINED

- A.1 Why Solar?
- **A.2 How Do Solar Panels Works?**
- A.3 How Will This System Reduce Energy Cost for us?
- A.4 What we offer?
- **B. OUR COMMITMENT IN SERVICE**
- C. OUR COMMITMENT TO QUALITY
- D. OUR COMMITMENT IN MAINTENANCE AND SUSTAINABILITY
- E. OUR TECHNICAL TEAM
- F. SAFETY PRACTICE
- G. JOB REFERENCE
 - **G.1 Green Cross RTS in Binh Duong Province.**
 - **G.2 II-VI RTS in Binh Duong Province.**
 - G.3 VBL RTS Project (Heineken Factory).
 - G.4 Sao Dau RTS Design Proposal in Dong Nai Province.
 - G.5 Bac Ning RTS Design Proposal in Bac Ninh Province.
 - G.6 Video of Latest Job Reference.



A.1 Why Solar?

The sun has produced energy for billions of years. We call this solar energy. Solar energy does not produce any pollutants and is one of the cleanest sources of renewable energy. It requires low maintenance and is easy to harness through solar photovoltaic technology (solar panels). As Asia typically receives abundant exposure to the sun, companies in Asia are in a unique position to positively reduce to their utility bills.


A.2 How Do Solar Panels Work?

- Solar photovoltaic (PV) technology was developed in the 1960's for space applications. This mature technology is now used in Commercial and Industrial rooftop applications. The PV modules convert the sun's energy into usable electricity. The PV system works in this way:
 - ➤ Solar PV modules are installed and positioned on the roof of buildings to get maximum solar radiation.
 - ➤ The energy hitting the modules is converted into Direct Current (DC) electricity.
 - The DC electricity flows through cables into inverters. These electrical devices convert DC electricity into Alternating Current (AC) electricity which is the same type used to power the majority of loads in buildings eg. machines, computers, lighting, A/C, etc.
 - ➤ The AC electricity is then used throughout the facility and can in some cases be exported back to the grid.
 - ➤ All generated AC electricity is tracked and easily accessible by the facility owner.



A.3 How Will This System Reduce Energy Cost For Us?

- ➤ We does not disconnect or replace your current utility connection. The system installed provides power to the facility and simply reduces the amount of energy taken from the grid.
- When the solar facility produces less energy than needed, the balance is drawn from the grid or Diesel generator. The facility remains connected to the grid as it was before.





A.4 What We Offer?

- ➤ ION M&E Company Limited specializes in providing solutions for investment, engineering, procurement, construction (EPC) of rooftop solar power system. Together with a team of experienced engineers, who have directly participated in engineering, we understand deeply the factors that make high quality and best investment efficiency.
- ➤ ION is built on the basis of core values with customer focus, reliable, professional, continuous improvement, strive non-stop for mission bring green energy to community, contributing to sustainable socio-economic development.

B. OUR COMMITMENT TO SERVICE

- ✓ Soil expertise: ION is focused on the development of a renewable energy ecosystem and provides a team of highly skilled engineers with extensive experience.
- ✓ Good reputation: ION always follows through on its commitments, ensuring the quality, safety, and aesthetics of each project completed.
- ✓ Attentive attitude: ION is dedicated to providing thoughtful services and advising customers on the best solution.



C. OUR COMMITMENT TO QUALITY

- ✓ Professional system design by a highly qualified and experienced team of engineers.
 Furthermore, the solar power system will be meticulously calculated so that it does not interfere with existing activities on the roof...
- ✓ Providing genuine, carefully selected materials: To ensure overall system quality, we carefully selects all materials from leading domestic and international prestigious brands. For main materials such as solar panels and inverters, in particular we only uses genuine products from leading, globally prestigious brands, and all products have Certificates of Origin (CO) and Certificates of Quality (CQ).
- ✓ Construction and installation meet design standards: ION's experienced construction engineers will ensure that technical standards are met following design drawings and standards such as ISO 9001:2015, ISO 14001:2015, and ISO 45001:2018. In particular, after construction, the solar power system will be checked by engineers using the specialized testing equipment to ensure safe operation of the system and effectiveness after handing over to the customer.

D. OUR COMMITMENT IN MAINTENANCE AND SUSTAINABILITY

OUR COMMITMENT TO YOU

- **✓** 10 years preventive maintenance service.
- ✓ 02 year system defects liabilities warranty.
- ✓ 06 years Inverter warranty.
- **✓** 10 years solar panel warranty.
- ✓ 24/7 standby emergency service.



E. OUR TECHNICAL TEAM

- Licensed Electrical Engineer by Energy Market Authority in Singapore
- Professional Engineer (Electrical) by Professional Engineer Board in Singapore
- Master Business Administration
- Certificate of Competence, Design & Installation of Grid Connected Photovoltaic Training course by Pusat Tenaga Malaysia (PTM) (16-27 June 2008) Cert: PTM-08/015
- Certificate in Construction Safety for Project Managers, 19 Jan 06 Feb 2009, approved by Ministry of Manpower in Singapore
- Certificate for CEO/Top Management (bizSAFE Level 1), 21 Sep 2018, approved by Ministry of Manpower in Singapore
- Certificate in Risk Management (bizSAFE Level 2), 18-19 June 2009, approved by Ministry of Manpower in Singapore
- Certified First Aider by Singaporean Red Cross Society 04 Feb 2009. Cert: 59022





Amega Precess Management Pte Ltd

GST & Company Registration No. 201209699W

Curriculum Vitea

Director



Er Tan Kok Ann

- Licensed Electrical Engineer by Energy Market Authority in Singapore.
- Professional Engineer (Electrical) by Professional Engineer Board in Singapore.
- Master Business Administration.
- Certificate of Competence, Design & Installation of Grid Connected Photovoltaic Training course by Pusat Tenaga Malaysia (PTM) (16-27 Jun 2008) Cert: PTM-08/015.
- Certificate in Construction Safety for Project Managers, 19 Jan –
 06 Feb 2009, approved by Ministry of Manpower in Singapore.
- Certificate for CEO/Top Management (bizSAFE Level 1), 21 Sep 2018, approved by Misnitry of Manpower in Singapore.
- Certificate in Risk Management (bizSAFE Level 2), 18-19 Jun 2009, approved by Ministry of Manpower in Singapore.





Amega Precess Management Pte Ltd

GST & Company Registration No. 201209699W

Curriculum Vitea

Experiences

	Exponential				
S/N	Project Description	Project Duration	Contract Value (Estimate)		
01	Project management and ensuring the smooth implementation of the underground cable tunnels for 400kV transmission cables. Singapore	03 years	S\$ 120m		
02	Renewal of 22kV service cables to Tg Pagar Conservation projects. Singapore	05 years	S\$ 1.2m		
03	22kV Temporary supplies to the construction of Tuas Power Station. Singapore	0.5 year	S\$ 1.1m		
04	Upgrading of supplies to offshore island and commissioning of new 22kV electrical substation. Singapore	03 months	S\$ 2.3m		
05	Installation and commissioning of 22kV supplies to factories in the Tuas development. Singapore	12 months	S\$ 3.3m		
06	Installation and commissioning of 15.66kWp PV system for private residence. Singapore	02 weeks	S\$ 150-200k		





Amega Precess Management Pte Ltd

GST & Company Registration No. 201209699W

Curriculum Vitea

Experiences

S/N	Project Description	Project Duration	Contract Value (Estimate)
07	71.4kWp Grid-connected PV system on the Malaysian Ener Singapore gy Commission Diamond Building, Kuala Lumpur, Malaysia (Surahanjaya Tenaga). Turnkey system design, simulation, equipment sizing and selection, supply and installation. Malaysia	02 months	RM 1.5-2.0m
08	300.37kWp grid-connected PV system on rooftop of REC Solar water factory. Turnkey system design, simulation, equipment sizing and selection, supply, installation and commissioning. Singapore	02 months	S\$ 2.5-3.0m
09	206.532kWp Grid-connected PV system for a carport in Laguna, Philipines. Turnkey system design, simulation, equipment sizing and selection, supply, installation and commissioning. Philippines	05 months	USD 1.1-1.2m





Amega Precess Management Pte Ltd

GST & Company Registration No. 201209699W

Curriculum Vitea

Experiences

S/N	Project Description	Project Duration	Contract Value (Estimate)
10	1088kWp Grid-connected PV system on ground mounted for Maan University in Jordan Turnkey system design, simulation, commissioning. Singapore.	02 months	USD 1.9m
11	Project & Technical Advisor to a consortium to develop a ground mounted 60 MWp Grid-connected PV system mounted in Bangladesh	12 months	USD 110m
12	Project & Technical Advisor to the EPC on the design, install and commission of roof and ground mounted of Grid-connected PV system in Singapore and Vietnam	Ongoing	More than USD 5m
13	Project & Technical Consultant to developer on the design, install and commission of ground mounted 60MW soar PV system for multiple sites in Singapore	Ongoing	More than USD 60m




F. SAFETY PRACTICE

1. Personal Protective Equipment (PPE)

Ensure that all employees have to equip all mandatory PPE.

Other PPE are required dependance on the method of statement, risk assessment (such as: leather gloves, leather apron, welding shield for welders)





F. SAFETY PRACTICE

2. Safety measures

Walking on the roof

Install Life line

Install barrier to cover the roof













G.1 GreenCross RTS in Binh Duong Province

G.1.1 General Brief

Project address: Green Cross Factory VSIP 01, Binh Duong Province.

Investor: Vietnam - Singapore Smart Energy Solutions (VSSES).

Solar PV System Size: 577 KWp.

Total Modules: 1300 Nos. Longi 445Wp - Model No. LR4-72HPH-445M.

Module Dimension (LxWxH): 2094x1038x35 mm, 23.5 kg.

Inverter 1: HUAWEI SUN2000-100KTL-M1.

Inverter 2: HUAWEI SUN2000-60KTL.



G.1 GreenCross RTS In Binh Duong Provice

G.1.2 Photos of Completion







G.2 II-VI RTS In Binh Duong Provice

G.2.1 General Brief

Project address: II-VI Factory VSIP 01, Binh Duong Province.

Investor: Vietnam - Singapore Smart Energy Solutions (VSSES).

Solar PV System Size: 638 KWp.

Total Modules: 1434 Nos. Longi 445Wp - Model No. LR4-72HPH-445M.

Module Dimension (LxWxH): 2094x1038x35 mm, 23.5 kg.

Inverter: HUAWEI SUN2000-100KTL-M1.



G.2 II-VI RTS In Binh Duong Provice

G.2.2 Photos of Completion







G.3 VBL RTS Project (Heineken Factory)

G.3.1 General Brief

Project address: Heineken Factory 12 Distric, HCM City.

Investor: Heineken Factory.

Solar PV System Size: 52.205 KWp.

Total Modules: 197Nos.TRINA 265Wp Multi-C Module.

Module Dimension (LxWxH): 1650x992x40 mm, 19.6 kg.

Inverter: SMA STP 20000TL.



G.3 VBL RTS Project (Heineken Factory)

G.3.2 Photos of Completion









G.4 Sao Dau RTS Design Proposal

Engineering, Procurement and Construction (EPC)

- 1. Design roof top solar system.
- 2. Supply and installation.
- 3. Testing and commissioning.
- 4. Handover to operation.
- 5. Defect liability warranty and maintenance proposal.



G.4 Sao Dau RTS Design Proposal

ASTRONERGY-CHINT solar system use as the base reference system of our solar system design

proposal:

- Solar panel: CHSM72M-HC-545W

- Solar Inverter: CPS SCA110KTL-DO/EU



CPS SCA110KTL-DO/EU


Chint Power Three-phase Inverter High Return of the Whole Life Cycle





G.4 Sao Dau RTS Design Proposal

Solar panel master plan



We Renew Energy

G. JOB REFERENCE

G.4 Sao Dau RTS Design Proposal

PVsyst Report Calculation data



PVsyst V7.2.0

VC0, Simulation date: 07/04/22 11:29 with v7.2.0 Project: Solar Dau Giay Factory

Variant: New simulation variant

Project summary

Geographical Site

DAU GIAY FACTORY

Vietnam

Situation

Altitude

Latitude Longitude 10.93 °N 107.15 °E 158 m

Time zone UTC+7

Meteo data

DAU GIAY FACTORY

Meteonorm 8.0 (1996-2015), Sat=100% - Synthetic

System summary

Grid-Connected System

Simulation for year no 1

Tables on a building

PV Field Orientation

Fixed plane

Tilt/Azimuth 1 / 180 °

Near Shadings Linear shadings User's needs
Unlimited load (grid)

Project settings

Albedo

System information

PV Array
Nb. of modules
Pnom total

960 units 523 kWp Inverters

Nb. of units Pnom total

3.6 units 360 kWac

1.453

0.20

Pnom ratio

Results summary

Produced Energy 738.6 MWh/year

Specific production

1412 kWh/kWp/year Perf. Ratio PR

78.01 %



G.4 Sao Dau RTS Design Proposal

PVsyst Report Calculation data

Main results

System Production

Produced Energy (P95)

Produced Energy (P50) 738.6 MWh/year Produced Energy (P90) 721 MWh/year

716 MWh/year

Specific production (P50) Specific production (P90)


Specific production (P95)

1412 kWh/kWp/year Performance Ratio PR


78.01 %

1378 kWh/kWp/year 1368 kWh/kWp/year

Normalized productions (per installed kWp)




Performance Ratio PR





G.5 Bac Ninh RTS Design Proposal

Solar panel master plan



Solar PV Layout of Master Plan

Single Line Diagram ACDB-Site 01



G.6 Video of Latest Job Reference.

